City of Wakefield

INVITATION TO BID

Repair of roads from emergency water line repair and winter damage.

April 27, 2020

City of Wakefield is accepting proposals for the reconstruction and resurfacing of attached list of repair sites at various locations throughout the City. All work is to be done according to Michigan Department of Transportation (MDOT) Specifications. Below is the scope of work may include earth excavation, curb/gutter/walk replacement, Saw cut existing HMA in a rectangular fashion to square up repair site, aggregate base, hot mix asphalt paving, the maintenance of traffic, traffic control, and restoration work in the City of Wakefield.

Specifications:

- Saw cut existing HMA in a rectangular fashion and remove. Remove broken and disturbed concrete curb & gutter as needed and replace all missing curb/gutter and walk.
- Repairs conducted on sites with emergency water repair: remove earth to within 12" of water main and compact every 6" to 95%. Backfill shall be class II sand. The top base layer will be 8" of 22A compacted to 98% and surfaced with 3" HMA 13A, or equal. All asphalt must come from an MDOT certified plant with a MDOT certified mix design.
- All manholes and Water valve boxes or curb stops must be adjusted. They must be flush with or slightly below (1/2") new pavement level.
- Traffic maintenance shall be according to the Michigan Manual of Uniform Traffic Control Devises (MMUTCD).
- Restoration of disturbed areas around the site consisting of topsoil, seed, and mulch.
- Payment shall be made by the lump sum per location.
- Contractor must furnish a list of Subcontractors and as to what portion of the work they are performing.

The City will provide a convenient location to dispose of spoils. Contractor shall be responsible to spread & grade spoils at disposal site.

Contractor must provide proof of appropriate insurance to perform the work.

Sealed proposals with the enclosed forms will be received at the City of Wakefield, 509 Sunday Lake Street, Wakefield, MI 49968 until 1:00 p.m. on May 11, 2020, at which time all proposals will be publicly opened and read aloud. Envelopes must be marked "Road Repair".

All work must be completed within 64 days of the notice to proceed. Notice to Proceed will be issued with award and signed contract.

The City of Wakefield reserves the right to reject any and/or all bids.

Location of Repair

	Street	Dimension
1	Sunday Lake Rd and Peirce	42’x20’
2	Ahola and Peirce	7’x13’
3	Charles Street	6’x24’
4	Ahola Ave	5’x12.5’
5	Ahola Ave	7’x6’
6	Third and Dewy	18’x16’
7	Anderson and Fourth	15’x14’
8	Castile Street	6’x16’
9	Park Street	6’x16’
10	Park Street	10’x21’
11	Harrison Street	11’x22’
12	Harrison Street	5’x14’
13	Chicago Mine Street	17’x20’
14	503 North Street (culvert crossing)	8’x19’
15	510 South Chicago Mine Rd	8’x20'
16	Crushee and Johns Road	11’x23'

City Staff will be available to visit each site and answer any question by appointment only. City Staff will be available Monday through Thursday 7:00AM CST to 3:00PM CST. Appointments my be scheduled by contacting the City Clerk at 906.229.5131 ext 1002 or email clerk@cityofwakefield.org